

Survey & REMONUMENTATION

\$7.00
\$2.00

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

SECTION

For corners in

Kent (County)	Located in: Oakfield Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>9W</u>	<u>M-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC 27 AM 8:20
REG. OF DEEDS

11672

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on March 26 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10	1837	G.L.O. Notes	Cathcart	Set Post
	1939	Witness Map	K.C. Surveyor	Conc. Monument
	1983	L.C.R.C. #3590	William Byl	Square Spike Over Top of Concrete Mon.
	1984	L.C.R.C. #3945	William Byl	Fnd. Spike in Mon. Box / Set K.C. Monument
	1994	L.C.R.C. #7263	Glaza & Associates	K.C. Monument

Note: This corner is common with A-10, T9N, R8W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 9/20/84 and was recorded per L.C.R.C. #3945.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10 Found a Standard Kent County Monument 2.5' ± South of the C/L of Beardslee Street (bit.) running East and West and 5' ± West of the C/L of Montcalm (gravel) running South per L.C.R.C. #3945 and #7263 as set by William Byl in place of a spike he found in a monument box.

L.C.R.C. #3945

L.C.R.C. #7263

Nail & tag, E. sd. Power pole N 00° E 43.74'
Nail & tag, S. sd. Power pole N 70° W 129.32'
Nail & tag, S. sd. Power pole S 50° W 152.03'
SW cor. fndn. Hse #11980 N 35° E 125.78'

Nail & K.C. remon tag in E side P. pole N00°E 43.74' (m. 43.71')
SW corner foundation of house #11980 N35°E 125.78' (m. 125.76')
Nail & K.C. remon tag in NW side P. pole S60°W 150.04' (m. 150.01')
Nail & K.C. remon tag in S side P. pole N60°W 125.89' (m. 125.85')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 Standard Kent County Monument

Nail & K.C. remon. tag on E side P. pole N 00° E 43.71'
Nail & K.C. remon. tag on NW side P. pole S 60° W 150.01'
Nail & K.C. remon. tag on S side P. pole N 60° W 125.85'
SW cor. fndn. hse. #11980 N 35° E 125.76'
Nail & K.C. remon. tag on N side P. pole S 70° E 262.53'
C/L of bit. road running E-W, North 2.5' ±
C/L of gravel road running S, East 5' ±



Signed by Randy J. Kolehouse Date 10-29-99
WILLIAMS & WORKS

Surveyor's Michigan License No. 25854

