

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00
\$2.00

SECTION

For corners in

KENT COUNTY

(County)

Located In: Corner Code #

1. Public Land Survey

T 9N R 11W M-6
T R common with
T 9N R 10W A-6

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:35
REG. OF DEEDS
Eric Standa

10581

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Kirk Breitels, in a field survey on Feb. 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6	1837	GLO	Brookfield	Set Post
	1973	LCRC #540	Spicer	"T" Iron
	1981	LCRC #2168	Jonker	Set Kent County Monument
	1994	LCRC #7063	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Harry Thubert

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10-1-81 and was recorded per LCRC #2168.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the "T" Iron he found. Said "T" Iron checks with LCRC #540.

LCRC #2168				LCRC #7063
Nail & Remon. tag 8" B. Elder	N16°E	37.56'	Nail & Remon. tag 15" B. Elder	N16°E 37.36'
Nail & Remon. tag 6" B. Elder	N60°W	14.65'	Nail & Remon. tag 8" Cherry	S60°W 32.81'
Nail & Remon. tag 6" Cherry	S60°W	32.87'	Nail & Remon. tag 18" B. Elder	S82°E 77.20'
Nail & Remon. tag 10" B. Elder	S82°E	76.93'	Nail & Remon. tag 10" Cherry	N60°W 7.25'
PK Nail in fence post	S42°W	51.32'	PK Nail in fence post	S42°W 51.37'
C/L creek is West 60' ±				

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Standard Kent County Monument				
Nail & KC Remon. tag E. side 18" Box Elder	N16°E	37.36'		
Nail & KC Remon. tag SE side 10" Cherry	S60°W	32.81'		
Nail & KC Remon. tag N. side 20" Box Elder	S82°E	77.20'		
Nail & KC Remon. tag S. side 12" Cherry	N60°W	7.25'		
PK Nail in face of fence post (leaning)	S42°W	51.60'		
C/L creek is West 60' ±				
C/L Porter Hollow Rd. is North 406' ±				



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98