

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

| | | |
|------------------------------------|------------|------|
| 1. Public Land Survey | T 9N R 11W | M 10 |
| | T 9N R 10W | A-10 |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 OCT -7 AM 10:15
REG. OF DEEDS
Luis Standa

10676

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | | | |
|-----------|---------------|------------|--------------------------------------|
| M-10 1837 | GLO | Brookfield | Set Post |
| | Kent Co. Wits | | PK in pavement |
| 1976 | LCRC #928 | McCloskey | Monument |
| 1981 | LCRC #1986 | Jonker | Set Kent County Monument in Mon. Box |
| 1994 | LCRC #7067 | Byl | Kent County Monument in Mon. Box |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/24/98
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8-26-81 and was recorded per LCRC #1986.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10 Found PK Nail at same location as Kent Co. Mon. per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Copper Conduit he found inside a Mon. Box. Said Copper Conduit checks LCRC's #928 & 1986.
LCRC #1986
Nail & Remon. tag 26" Box Elder S38°E 120.5'
Nail & Remon. tag 14" Maple S88°E 69.16'
Nail & Remon. tag 9" Locust N75°W 40.9'
Nail & Remon. tag 6" Oak N43°W 41.05'
C/L traveled way, Easterly 6' ±
LCRC #7067
Nail & Remon. tag 33" Box Elder S38°E 120.40'
Nail & Remon. tag 18" Maple S88°E 69.16'
Nail & Remon. tag 12" Locust N75°W 40.91'
Nail & Remon. tag 10" Oak N43°W 41.20'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 Standard Kent County Monument

| | | |
|--|-------|---------|
| Nail & KC Remon. tag W. side P. Pole | S20°W | 150.96' |
| Nail & KC Remon. tag S. side P. Pole | S90°W | 58.78' |
| Nail & KC Remon. tag SW side 33" stump | S38°E | 120.32' |
| Nail & KC Remon. tag S. side 18" stump | S88°E | 69.12' |
| Nail & KC Remon. tag E. side P. Pole | N25°W | 134.71' |
| Concrete Monument - West | | 60.00' |



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 9/24/98