

**SURVEY &
MONUMENTATION**

KENT COUNTY REMONUMENTATION

**\$7.00
\$2.00**

JAN 24 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T	9N	R	10W	B-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 DEC 20 AM 8:36
REG. OF DEEDS
Luigi Bond
8762

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Kirk Breitels, in a field survey on **Oct. 31**, 19 **95**

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	(19)		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- B-8 1837 GLO Not Set
- 1932-57 Williams & Works Accepted fence corner for Center - set Iron
- 1960 Kent Co. Wit. Iron at fence corner
- 1968 Williams & Works Fence Corner (prev. Iron gone) - Found Iron 9' South
- 1979 Survey Byl Computed intersection of 1/4 lines
- 1980 Survey Hackbardt Computed intersection of 1/4 lines
- 1987 Survey W. Glaza Iron at Center

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/30/95
CHAIRMAN *Harold Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-8 Found 4 Irons in vicinity of Center of Section.
- 1. Iron Pipe w/fitting at approximate fence cor. (fence lying down) 2.9' W. & 5.4' N. of "X" 1/4 lines
- 2. Rerod at approx. fence cor. 2.7' W. & 5.1' N. of "X" 1/4 lines.
- 3. Iron Pipe (8.1' S. of Iron #1) 3.2' W. & 2.7' S. of "X" 1/4 lines.
- 4. Capped Rerod (Glaza) 1.5' E. & 0.3' S. of "X" 1/4 lines.

Measurements and angles/bearings from surveys by Byl, Hackbardt, All Points, W. Glaza, E. Glaza for approximately 25 surveys in Sec. 19 all compute to the intersection of 1/4 lines (measurements & bearings on 1987 W. Glaza survey fit comp. "X" 1/4 lines better than the Iron found). Given the extensive use of the intersection of 1/4 lines, the intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-8 Set Standard Kent County Monument at the intersection of 1/4 lines
- Set Nail & KC Remon. tag N. side 18" Oak S90°W 7.16'
- Set Nail & KC Remon. tag W. side 18" Oak N15°E 19.57'
- Set Nail & KC Remon. tag SE side 24" Oak N45°E 14.41'
- Set Nail & KC Remon. tag N. side 8" Pine S75°E 24.55'
- Set Nail & KC Remon. tag W. side 10" Pine S10°E 30.61'
- Set Nail & KC Remon. tag NW side 10" Oak S40°W 26.47'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 12/4/95