

MAY 22 2000

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Courtland Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>10W</u>	<u>C-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 OCT 15 AM 8:03

11277

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 25 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-1	1837	G.L.O. Notes	Cathcart	Set Post
	1939	Witness Map	K.C. Surveyor	Concrete Monument
	1986	L.C.R.C. #4433	R. Kolehouse	Fnd. Bt. Spike over Conc. Mon. / Set K.C. Monument
	1993	L.C.R.C. #6658	John Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/25/99  
CHAIRMAN [Signature]



Note: This corner is not common with C-13, T10N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse in May of 1986 and was recorded per L.C.R.C. #4433.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 Found a Standard Kent County Monument on the C/L of 16 Mile Road (bit.) running East and West, 2.0' East of Ritchie Avenue (bit.) running South, 112.0' ± East of Ritchie Avenue (bit.) running North and 112.26' East of Section 31, T10N, R10W, per L.C.R.C.'s #4433 and #6658 as set by Randy Kolehouse in place of a boat spike he found over a concrete monument on the South line of Section 31, T10N, R10W, which checked with the K.C. Surveyor's records.

L.C.R.C. #4433

L.C.R.C. #6658

Nail & K.C. Remon. tag in E. side 18" Pine S 30° W 89.80'

Nail & K.C. Remon. tag in top C/L 1' wood cor. fence post S 45° E 40.0'

K.C. Mon. at SE cor. section 31 T10N R10W West 112.0'

Nail & K.C. Remon. Tag in E side 20" Pine S 30° W 89.53' (m. 89.43')

Nail & K.C. Remon. Tag in top C/L 1' wood cor. fence post S 45° E 39.90' (39.91')

SE cor. block bldg. fnd. North 130.84' (m. 130.77')

K.C. Mon. SE cor. Sec. 31, 10-10 West 112.00' (m. 112.26')

On C/L bit. E-W; C/L bit. South, W 2' +/-

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 Standard Kent County Monument

Nail & K.C. remon. tag on E side 22" Pine S 30° W 89.43'

Nail & K.C. remon. tag on top C/L 1' wood cor. fence post S 45° E 39.91'

Nail & K.C. remon. tag on S side 12" Cherry N 75° E 140.61'

Nail & K.C. remon. tag on N side 18" Pine S 80° W 165.94'

SE cor. block bldg. North 130.77'

On C/L of bit. road running E-W

C/L of bit. road running S, West 2.0'

C/L of bit. road running N, West 112.0' ±

K.C. Mon., C-13, T10N, R10W, West 112.26'

Signed by Randy J. Kolehouse Date 3/30/99

EARTH TECH

Surveyor's Michigan License No. 25854

