

**SURVEY & REMONUMENTATION**

**\$7.00**  
**\$2.00**

**MAR 03 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 NOV 14 AM 9:01  
REC. OF DEEDS  
*Lucy Bond*

For corners in

**SECTION**

Kent (County)	Located in:	Courtland Township	Corner Code #
1. Public Land Survey	T <u>9N</u>	R <u>10W</u>	<u>C-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

**10320**

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on July 15 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C-13	1831	G.L.O. Notes	Mullett	Set Post
	1954-69	Notes	Williams & Works	Iron
	1960	Witness Map	K.C. Surveyor	Iron
	1984	L.C.R.C. #3986	William Byl	Fnd. 1-1/2" Iron / Set K.C. Monument
	1988	L.C.R.C. #4808	J. Bueche	K.C. Monument

Note: This corner is not common with C-1, T8N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 10/8/84 and was recorded per L.C.R.C. #3986.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C-13 Found a Standard Kent County Monument 100' ± South of the C/L of 10 Mile Road (bit.) running East and West and at South end of wood fence running North per L.C.R.C.'s #3986 and #4808 as set by William Byl in place of a 1-1/2" iron he found which checked the the K.C. Surveyor's records and the 1954-69 notes of Williams & Works.

L.C.R.C. #3986

L.C.R.C. #4808

Nail & tag, N. sd. 12" Tamarack S 70 W 44.15'  
Nail & tag, E. sd. 8" Oak N 20 W 21.10'  
Nail & tag, S. sd. 12" Poplar N 80 E 42.99'  
Nail & tag, E. sd. 16" Tamarack S 15 E 27.20'  
South face of fence post N 10 E 0.70'

Nail & tag N sde. 14" Tamarack S 70 W 44.18'  
Nail & tag E sde 10" Oak N 20 W 21.10'  
Nail & tag E sde 14" Poplar N 80 E 42.99'  
Nail & tag E sde 18" Tamarack S 15 E 27.20'  
South face of fence post N 10 E .70'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-13 Standard Kent County Monument

Nail & K.C. remon. tag on N side 14" Tamarack S 70° W 44.18'  
Nail & K.C. remon. tag on E side 10" Oak N 20° W 21.10'  
Nail & K.C. remon. tag on E side 14" Poplar N 80° E 42.99'  
Nail & K.C. remon. tag on E side 18" Tamarack S 15° E 27.20'  
K.C. Mon., C-1, T8N, R10W, East 184.88'



Signed by Randy J. Kolehouse  
EARTH TECH

Date 9/23/97

Surveyor's Michigan License No. 25854