

SURVEY &
REMONUMENTATION

MAY 22 2000

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

<u>Kent</u> (County)	Located in:	Courtland Township	Corner Code #
1. Public Land Survey	T <u>9N</u>	R <u>10W</u>	<u>D-1</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 OCT 15 AM 8:03

11288

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on February 10, 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore, as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1 This corner was not originally set by the G.L.O.

1975	L.C.R.C. #3413	Glaza & Associates	N/A
1986	L.C.R.C. #4434	R. Kolehouse	Fnd. 3/4" Iron / Set K.C. Monument
1993	L.C.R.C. #6659	John Bueche	K.C. Monument

Note: This corner is not common with D-13, T10N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse in May of 1986 and was recorded per L.C.R.C. #4434.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/29/99
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Kent County Monument was not found. Monument was reset per witnesses from L.C.R.C.'s #6659, #4434 and #3413 0.5' ± South of the C/L of 16 Mile Road (bit.) running East and West.

L.C.R.C. #4434

L.C.R.C. #6659

Nail & K.C. Remon. tag in SE face 24" Hick. N 42° W 41.19'
Nail & K.C. Remon. tag in N. side P. Pole S 70° W 146.20'
Steel fence post S 15° E 33.43'
K.C. Mon. at S 1/4 cor. sec. 32 T10N R10W West 80.25'

Steel fence post S 15° E 33.43'
Nail & K.C. Remon. Tag in SE fce 24" Hickory N 42° W 41.00' (m. 40.83')
Nail & K.C. Remon. Tag in N side PP S 70° W 146.31' (m. 146.25')
NE cor. of hse. S 55° W 228.01' (m. 228.16')
PK in face of PP N 05° W 167.88' (m. 168.03')
K.C. Mon. (S 1/4 32, 10-10) West 80.34' (m. 80.48')
C/L gravel road E-W, S 2'+/-

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Reset a Standard Kent County Monument - Also Set a New Monument Box

Nail & K.C. remon. tag on SE side 26" Hickory N 42° W 40.93'
PK nail S face P. pole N 05° W 168.03'
NE cor. hse. Fndn. S 55° W 228.16'
Nail & K.C. remon. tag on SE side 10" Elm N 60° E 79.96'
Nail & K.C. remon. tag on N side P. pole S 70° E 164.15'

Nail & K.C. remon. tag on N side P. pole S 70° W 146.25'
C/L of bit. road running E-W, North 0.5'±
K.C. Mon., D-13, T10N, R10W, West 80.48'

Signed by [Signature] Date 9-27-99

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854

