

MAY 22 2000

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Courtland Township	Corner Code #
1. Public Land Survey	T <u>9N</u>	R <u>10W</u>	<u>D-5</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 OCT 15 AM 8:04

11291

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randy Kolehouse, in a field survey on February 10 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5	1837	G.L.O. Notes	Cathcart	Set Post
	1963	Witness Map	K.C. Surveyor	1" Iron - Axle
	1983	L.C.R.C. #3420	Glaza & Associates	N/A
	1983	L.C.R.C. #3637	John Bueche	Fnd. Form Pin in Mon. Box / Set K.C. Monument
	1988	L.C.R.C. #4810	John Bueche	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 11/11/83 and was recorded per L.C.R.C. #3637.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 Monument had been removed or destroyed. Found a PK nail 1.0' South of the C/L intersection of 14 Mile Road (M-57) (bit.) running East and West and Tefft Road (gravel) running South per witnesses remaining from L.C.R.C.'s #3420, #3637 and #4810.

L.C.R.C. #3637

SE cor. hse. foundation N 10° W 86.44'
SW cor. hse. foundation N 35° W 98.04'
C/L blacktop road E - W is North 1'
On C/L gravel road South

L.C.R.C. #4810

SE cor hse fndn N 10° W 86.44' (m. 86.46')
SW cor hse fndn N 35° W 98.04' (m. 98.00')
C/L bit rd E-W is N 1'
On C/L gravel rd S

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 Replaced PK Nail with a Standard Kent County Monument

SE cor. hse. fndn. N 10° W 86.46'
SW cor. hse. fndn. N 35° W 98.00'
Nail & K.C. remon. tag on SE side P. pole S 70° W 224.20'
Nail & K.C. remon. tag on E side P. pole S 20° E 185.75'
C/L of bit. road running E-W, North 1.0'
On C/L of gravel road running South

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/25/99

CHAIRMAN *[Signature]*

Signed by Randy J Kolehouse

EARTH TECH

Date 3/30/99

Surveyor's Michigan License No. 25854

