

\$7.00
\$2.00

SURVEY &
MONUMENTATION

KENT COUNTY REMONUMENTATION

JAN 24 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

- | | | | | |
|------------------------------------|---|----|-------|-----|
| 1. Public Land Survey | T | 9N | R 10W | F-8 |
| | T | | R | |
| | T | | R | |
| | T | | R | |
| 2. Property Controlling in Section | S | T | R | |
| | S | T | R | |
| 3. Miscellaneous | S | T | R | |
| Property in Section | S | T | R | |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 SEP 14 PM 12:35
8708

REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on June 28, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-8 1837 GLO Not Set
- 1976 Survey Ed Glaza "Center"
- 1983 Survey All Points "True Center"
- 1994 Survey Roosien "Center" (same dimensions as All Points survey)

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/24/95
CHAIRMAN Harry Stuber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-8 Found Capped Rerod (All Points) 0.4' S. & 0.1' W. of true intersection of 1/4 lines. Said Rerod is on fence to West and field division North. Also found Capped Rerod (Glaza) 1.2' S. & 2.4' W. of All Points Iron.

The Capped Rerod (All Points) is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-8 Set Standard Kent County Monument in place of Capped Rerod (All Points).
 - Set Nail & KC Remon. tag NE side 32" Elm N70°W 17.31'
 - Set Nail & KC Remon. tag W. side 20" Elm S30°E 242.6'
 - Set Nail & KC Remon. tag E. side 15" Elm S10°E 15.61'
 - Set Nail & KC Remon. tag E. side 12" Elm S25°W 21.36'
 - Capped Rerod (Glaza) S70°W 2.63'
 - On fence & brush line S & W; On field division N.



Signed by Kirk Breitels

Date 9/8/95

Surveyor's Michigan License No. 30077