

\$7.00
\$2.00

SURVEY &
MONUMENTATION

KENT COUNTY REMONUMENTATION

JAN 24 1996

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	9N	R	10W	F-12
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 SEP 14 PM 12:35

REG. OF DEEDS
8704

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on June 26, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-12 1837	GLO		Not Set
1939	Kent Co. Wit.		1/2" Solid Iron
1980	LCRC #2088	Jonker	Found Rerod & cap #9548 (Glaza)
			8" W. Cherry SE 11.24'
			12" Hickory E 33.67'
			Quad Clump W. Cherry W 31.04'
1986	Survey	Glaza	Center per LCRC #2088

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-12 Found Rerod & Cap #9548 on E. side of 30" Nut Tree. Said Rerod agrees with witnesses from LCRC #2088. No witnesses from Kent Co. remain. Said Rerod is 0.9' E. and less than 0.1' S. of the true intersection of 1/4 lines. Measurements and angles using said Rerod agree more or less with surveys by Nederveid & Jonker, Glaza, and Roosien.

The Rerod and Cap #9548 is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/29/95
CHAIRMAN [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-12 Set "Kent Co. Remon."	cap on rerod on E. side of 40" Nut Tree	in place of cap #9548
Set Nail & KC Remon. tag (vertical)	in root of 40" Nut Tree	N00°E 0.57'
Set Nail & KC Remon. tag	N. side Tw. 12" Hickory	S90°E 32.02'
Set Nail & KC Remon. tag	W. side 6" Cherry	S00°E 21.30'
Set Nail & KC Remon. tag	SW side 12" Cherry	S50°E 11.16'

Signed by [Signature]

Date 9/8/95

Surveyor's Michigan License No. 30077

