

MAY 22 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Table with columns: Kent (County), Located in: Courtland Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

REG. OF DEEDS

Handwritten signature

1999 OCT 15 AM 8:04
STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

11316

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on January 21 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns: G-1, 1837, 1898, 1951, 1986, 1993, G.L.O. Notes, Cathcart, Williams & Works, K.C. Surveyor, R. Kolehouse, John Bueche, Set Post, N/A, 3/4" Iron, Fnd. 3/4" Iron in Mon. Box / Set K.C. Monument, K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED

CHAIRMAN

Note: This corner is not common with G-13, T10N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse in May of 1986 and was recorded per L.C.R.C. #4437.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 Found a Standard Kent County Monument (on the Township line) at the C/L intersection of Myres Lake Avenue (bit.) running North and South and 16 Mile Road (gravel) running East and West per L.C.R.C.'s #4437 and #6662 as set by Randy Kolehouse in place of a 3/4" iron he found in a monument box 0.35' North of the Township line which checked the K.C. Surveyor's records.

L.C.R.C. #4437

L.C.R.C. #6662

Nail & K.C. Remon. tag in N. side 16" Walnut S 70° W 83.00'
Nail & K.C. Remon. tag in W. side 10" Ash N 40° E 63.58'
K.C. Monument at SE cor. section 33 T10N, R10E West 23.2'

Nail & K.C. Remon. Tag in N side 10" Poplar S 65° E 71.03' (m. 70.98')
Nail & K.C. Remon. Tag in W side 6" Elm N 40° W 55.94' (m. 55.91')
Nail & K.C. Remon. Tag in N side 18" Walnut S 70° W 83.00' (m. 83.01')
Nail & K.C. Remon. Tag in W side 12" Ash N 40° E 63.57' (m. 63.55')
K.C. Mon. (SE 33, 10-10) West 23.28' (m. 23.22')
On C/L bit. N-S; on C/L bit.-gravel E-W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 Standard Kent County Monument

Nail & K.C. remon. tag on N side twin 30" Oak S 80° E 90.28'
Nail & K.C. remon. tag on W side 8" Elm N 40° W 55.91'
Nail & K.C. remon. tag on N side 22" Walnut S 70° W 83.01'
Nail & K.C. remon. tag on W side 12" twin Ash N 40° E 63.55'
Nail & K.C. remon. tag on N side 10" Poplar S 65° E 70.98'

On C/L of bit. road running N-S
On C/L of gravel road running E-W
K.C. Mon., G-13, T10N, R10W, West 23.22'

Signed by Randy J. Kolehouse

Date 3/30/99

Surveyor's Michigan License No. 25854

