

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

SECTION

Table with columns: Kent (County), Located in: Courtland Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

REG. OF DEEDS

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 OCT 15 AM 8:05

11338

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on February 15 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns: Year, G.L.O. Notes, Cathcart, Set Post. Rows list years from 1837 to 1991 and corresponding monument types like Set Post, Leaded Stone, Concrete Monument, etc.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse on 8/3/85 and was recorded per L.C.R.C. #4302.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3 Found a Standard Kent County Monument on the C/L of Pine Lake Avenue (bit.) extended South and the C/L of 15 Mile Road (bit.) extended East per L.C.R.C.'s #4302 and #6253 as set by Randy Kolehouse in place of a concrete monument he found which checks the 1880 thru 1923 notes of Williams & Works and the K.C. Surveyor's records.

L.C.R.C. #4302

L.C.R.C. #6253

- Nail & K.C. Remon. tag in N. side Tri. 12" Oak S 85° W 27.90'
Nail & K.C. Remon. tag in SW side 6" Ash S 65° E 39.33'
Nail & K.C. Remon. tag in S. side 8" Ash N 75° E 30.97'
Nail & Remon tag in NW side 10" Ash 5' high N 46 E 31.00'
Nail & Remon tag in S side 8" Ash 5' high S 83 E 39.26' (m. 39.27')
Nail & Remon tag in W side 10" Oak 5' high S 17 E 29.55'
Nail & Remon tag in N side 16" Tri Oak 3' high S 60 W 27.87' (m. 27.89')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3 Standard Kent County Monument

- Nail & K.C. remon. tag on NW side 10" Ash (5' up) N 45° E 31.00'
Nail & K.C. remon. tag on S side 8" Ash (5' up) S 83° E 39.27'
Nail & K.C. remon. tag on W side 10" Oak (5' up) S 17° E 29.55'
Nail & K.C. remon. tag on N side 16" triple Oak (3' up) S 60° W 27.89'
On C/L of bit. road extended South
On C/L of bit. road extended East

P.A. 345 1990 KENT COUNTY

PEER APPROVED

CHAIRMAN

Signed by Randy J. Kolehouse
EARTH TECH
Surveyor's Michigan License No. 25854

Date 3/30/99

