

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Courtland Township	Corner Code #
1. Public Land Survey	T <u>9N</u>	R <u>10W</u>	<u>I-9</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REG. OF DEEDS

*[Handwritten Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 OCT 15 AM 8:06

11344

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 11 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-9	1837	G.L.O. Notes	Cathcart	Set Post
	1963	Witness Map	K.C. Surveyor	3/4" Iron
	1972	L.C.R.C. #292	Medema, Van Kooten & Assoc.	3/4" Iron in Mon. Box
	1982	L.C.R.C. #3285	C. Hay	Fnd. 3/4" Iron in Mon. Box / Set K.C. Monument
	1991	L.C.R.C. #6248	C. Marschall	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by C. Hay on 2/15/82 and was recorded per L.C.R.C. #3285.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 Found a Standard Kent County Monument in a monument box on the C/L of Young Avenue (bit.) running North and South per L.C.R.C.'s #3285 and #6248 as set by Clayton Hay in place of a 3/4" iron he found in a monument box which checked L.C.R.C. #292 and the K.C. Surveyor's records.

L.C.R.C. #3285

Nail and Remon. Tag in East side of 12" W. Cherry, N 17° W 85.15'  
Nail and Remon. Tag in East side of 12" Twin Oak, N 9° W 141.82'  
Nail and Remon. Tag in South side of Cons Power pole, N 90° E 39.75'

L.C.R.C. #6248

Nail & Tag E sd. Twin 18"-12" Oak N 9 W 141.74' (m. 141.75')  
Nail & Tag NE sd. 20" Cherry N 17 W 84.95'  
Nail & Tag S sd. 16" Maple N 58 W 87.66'  
Nail & Tag S sd. P. Pole N 90 E 39.72' (m. 39.68')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Standard Kent County Monument in a Monumet Box

Nail & K.C. remon. tag on E side 18" Oak N 09° W 141.75'  
Nail & K.C. remon. tag on NE side 20" Cherry N 17° W 84.95'  
Nail & K.C. remon. tag on S side 16" Maple N 58° W 87.66'  
Nail & K.C. remon. tag on S side P. pole N 90° E 39.68'  
On C/L of bit. road running N-S

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/25/99  
CHAIRMAN [Signature]

Signed by

[Signature: Randy Kolehouse]  
EARTH TECH

Date

3/30/99

Surveyor's Michigan License No.

25854

