

MAY 22 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Courtland Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>10W</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 OCT 15 AM 8:06
REG. OF DEEDS

11346

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on January 7 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11	1837	G.L.O. Notes	Cathcart	Set Post
	N/A	Witness Map	K.C. Surveyor	Iron
	1979	L.C.R.C. #1255	Williams & Works	1-1/2" Solid Iron
	1983	L.C.R.C. #3495	Williams & Works	Fnd. 3/8" Iron Pipe in Mon. Box / Set K.C. Mon. in Mon. Box
	1991	L.C.R.C. #6246	C. Marschall	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 7/28/83 and was recorded per L.C.R.C. #3495.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Found a Standard Kent County Monument on the C/L intersection of Young Avenue (bit.) running North and South and 11 Mile Road (bit.) running West per L.C.R.C.'s #3495 and #6246 as set by Williams & Works in place of a 3/8" iron pipe they found in a monument box which checked L.C.R.C. #1255 and the K.C. Surveyor's records.

L.C.R.C. #3495

L.C.R.C. #6246

Nail & KC.Reмон.tag in NW side Fence Post S.50°W. 59.63'
Nail & KC.Reмон.tag in NW side Fence Post N.40°E.53.31'
Nail & KC.Reмон.tag in SW side Gate Post S.42°E. 48.96'

Nail & Tag SW sd. Gate Post S 42 E 48.93' (m. 49.07')
Nail & Tag NW sd. Fence Post N 40 E 53.33' (m. 53.42')
Nail & Tag NW sd. Fence Post S 32 W 63.97' (m. 63.99')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Standard Kent County Monument

Nail & K.C. remon. tag on NE side 6" twin Maple N 50° W 90.22'
Nail & K.C. remon. tag on NW side fence post N 40° E 53.42'
Nail & K.C. remon. tag on SW side fence post S 42° E 49.07'
Nail & K.C. remon. tag on NW side fence post S 32° W 63.99'
Nail & K.C. remon. tag on NW side fence post S 50° W 60.55'
On C/L "X" of bit. roads running N-S-W

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/25/99

CHAIRMAN Randy Kolehouse

Signed by Randy J. Kolehouse
EARTH TECH

Date 3/30/99

Surveyor's Michigan License No. 25854

