

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

MAR 03 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 NOV 14 AM 9:01  
REG. OF DEEDS  
*Luci Sand*

SECTION

For corners in Kent (County) Located in: Courtland Township Corner Code #

1. Public Land Survey T 9N R 10W I-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**10326**  
Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on July 14 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-13	1831	G.L.O. Notes	Mullett	Set Post
	1943-59	Witness Map	K.C. Surveyor	Monument Box
	1972	L.C.R.C. #221	Williams & Works	Monument Box
	1978	L.C.R.C. #1107	Exxel Engineering	1/2" Iron in Mon. Box
	1981	L.C.R.C. #1724	Williams & Works	Fnd. 1/2" Iron / Set K.C. Monument
	1991	L.C.R.C. #6244	Chris Marschall	K.C. Monument

Note: This corner is not common with I-1, T8N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 1/8/81 and was recorded per L.C.R.C. #1724.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-13 Found a Standard Kent County Monument at the C/L intersection of 10 Mile Road (bit.) running East and West and Young Road (bit.) running North per L.C.R.C.'s #1724 and #6244 as set by Williams & Works in place of a 1/2" iron along side of a 1-1/2" iron they found in a monument box which checked L.C.R.C.'s #1107, #221, and the K.C. Surveyor's records.

L.C.R.C. #1724 L.C.R.C. #6244

- K.C. Remon. Tag & Nail in NW Side 22" Tri. B. Elder N 70°E 76.24' Nail & Tag W sd. 48" Box Elder N 57 E 75.98'
- K.C. Remon. Tag & Nail in SE Side P. Pole N 30°E 101.13' Nail & Tag E sd. P.P. N 20 E 101.07'
- K.C. Remon. Tag & Nail in E Side P. Pole N 40°W 96.18' Nail & Tag NE sd. U.P. N 50 W 96.05'
- K.C. Remon. Tag & Nail in N Side 26" Twin Oak S 85°W 126.88' Nail & Tag NW sd. 22" Oak S 47 W 41.14'
- K.C. Remon. Tag & Nail in SE Side 18" Oak S 55°W 41.15' Nail & Tag N sd. 28"-32" Twin Oak S 78 W 126.64'
- Mon I-1 8N 10W N 90 E 131.96'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- I-13 Standard Kent County Monument
- Nail & K.C. remon. tag on W side 48" Box Elder N 57° E 75.98'
  - Nail & K.C. remon. tag on E side P. pole N 20° E 101.07'
  - Nail & K.C. remon. tag on NE side U. pole N 50° W 96.05'
  - Nail & K.C. remon. tag on NW side 22" Oak S 47° W 41.14'
  - K.C. Mon., I-1, T8N, R10W, East 131.96'



Signed by *Randy J. Kolehouse* Date 9/23/97

Surveyor's Michigan License No. 25854

