

112

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

SECTION

For corners in

Kent (County)	Located in: Courtland Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>10W</u>	<u>J-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 1999 OCT 15 AM 9:06

11348

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on February 11 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1 This corner was not originally set by the G.L.O.

1966	Witness Map	K.C. Surveyor	N/A
1972	L.C.R.C. #187	Williams & Works	Iron
1979	L.C.R.C. #1280	G. Hackbardt	1" Iron
1986	L.C.R.C. #4448	R. Kolehouse	Fnd. 1" Iron / Set K.C. Monument

Note: This corner is not common with J-13, T10N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse in May 9f 1986 and was recorded per L.C.R.C. #4448.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 Found a broken Standard Kent County Monument (on the Township line) on the C/L of 16 Mile Road (gravel) running East and West, on line of a tree row running South, per L.C.R.C. #4448 as set by Randy Kolehouse on the Township line 2.05' North of the 1.0" iron he found which checked L.C.R.C.'s #1280, #187 and the K.C. Surveyor's records.

L.C.R.C. #4448

- Nail & K.C. Remon. tag in W. side 6" Hick. S 05° E 62.60' (m. 62.66')
- Nail & K.C. Remon. tag in W. side 14" Oak S 35° E 29.21' (m. 29.13')
- Nail & K.C. Remon. tag in NE side 12" Oak S 55° E 46.55' (m. 46.57')
- Nail & K.C. Remon. tag in N. side twin 10" Oak S 80° E 74.51' (m. 74.49')
- Iron 2.05' South (m. 2.07')
- K.C. Mon. at S 1/4 cor. sec. 35 T10N R10W West 229.0' (m. 228.85')

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 2/23/99
 CHAIRMAN *[Signature]*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 Replaced a Standard Kent County Monument

- Nail & K.C. remon. tag on W side 10" Hickory S 06° E 62.66'
- Nail & K.C. remon. tag on W side 18" Oak S 35° E 29.13'
- Nail & K.C. remon. tag on NE side 14" Oak S 55° E 46.57'
- Nail & K.C. remon. tag on N side twin 12" Oak S 80° E 74.49'
- Nail & K.C. remon. tag on E side twin 24" Oak N 40° W 129.40'
- Iron South 2.07'; Perod South 33.12'

- On C/L of gravel road running E-W
- On tree row running S
- K.C. Mon., J-13, T10N, R10W, West 228.85'

Signed by *[Signature]*
 EARTH TECH

Date 3/30/99

Surveyor's Michigan License No. 25854

