

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in SECTION

Table with columns: Kent (County), Located in: Courtland Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., Private Claims.

STATE OF MICHIGAN COUNTY OF KENT RECEIVED FOR RECORD 1999 OCT 15 AM 8:06

11350

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on February 15 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns: Date, Description, Location, Monument Type. Rows include 1837 G.L.O. Notes Cathcart Set Post, 1966 Witness Map K.C. Surveyor Iron, 1973 L.C.R.C. #516 Exxel Engineering 1" Iron, 1982 L.C.R.C. #3050 Jonker Land Survey Fnd. 1" Iron Pipe / Set K.C. Monument, 1991 L.C.R.C. #6242 C. Marschall K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 8/2/82 and was recorded per L.C.R.C. 3050.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3 Found a Standard Kent County Monument at the Southeast corner of the woods, on line of a tree row running West, per L.C.R.C.'s #3050 and #6242 as set by Rob Jonker in place of a 1" round Iron pipe he found 1.2" below grade which checked L.C.R.C. #516 and the K.C. Surveyor's records.

Table with columns: L.C.R.C. #, Description. Rows include L.C.R.C. #3050 Remon. tag on E side 4" Maple N15°W 45.47', L.C.R.C. #6242 Nail & Tag S. sd. 10" Cherry N 50 W 9.82' (m. 9.78'), Nail & Tag S. sd. 12" Maple N 85 W 44.49' (m. 44.46'), Nail & Tag E. sd. 8" Maple (4' above ground) N 15 W 45.47', Nail & Tag E. sd. Twin 6" & 3" Maple N 01 W 39.18'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3 Standard Kent County Monument
Nail & K.C. remon. tag on S side 10" Cherry N 40° W 9.78'
Nail & K.C. remon. tag on S side 12" Maple N 85° W 44.46'
Nail & K.C. remon. tag on E side 8" Maple N 15° W 45.47'
Nail & K.C. remon. tag on E side 8" Maple N 01° W 39.18'
On tree row running W

P.A. 345 1990 KENT COUNTY PEER APPROVED 2/25/99 CHAIRMAN Randy Kolehouse

Signed by Randy Kolehouse

Date 3/30/99

Surveyor's Michigan License No. 25854

