

DOCUMENT

KENT COUNTY REMONUMENTATION

JAN 24 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)

Located In:

Corner Code #

1. Public Land Survey	T	9N	R	10W	J-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous	S		T		
Property in Section	S		T		

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 95 OCT 24 PM 4:13
 REG. OF DEEDS
Lucy St. Grand
 8720
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on June 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-8 1837 GLO Not Set
 1983-87 Surveys All-Points PK Nail at int. 1/4 lines
 8" Ash N51°W 31.49'
 8" Locust N40°W 45.19'
 6" Hickory N45°E 60.65'

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 8/24/95
 CHAIRMAN *Harry Hubell*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-8 Found PK Nail per All-Points Surveys. Said PK is less than 0.1' S. & E. from the true intersection of 1/4 lines. Said PK Nail fits remaining 1983 witnesses from All-Points ± and is on brush line to South.

The PK Nail is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-8 Set Standard Kent County Monument in place of the PK Nail.
 Set Nail & KC Remon. tag N. side P. Pole S80°W 180.63'
 Set Nail & KC Remon. tag N. side P. Pole S70°E 116.65'
 Set Nail & KC Remon. tag S. side 12" Elm N50°W 46.63'
 Set Nail & KC Remon. tag NE side 10" Locust N40°W 45.08'
 Set Nail & KC Remon. tag W. side 20" Elm N10°W 31.07'
 Set Nail & KC Remon. tag SE side 8" Hickory N50°E 60.80'



Signed by *Kirk Breitels*
 30077

Date 10/20/95

Surveyor's Michigan License No. _____