

7/2

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

REG. OF DEEDS

Handwritten signature/initials

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 OCT 15 AM 8:07

SECTION

For corners in

Table with columns: Kent (County), Located in: Courtland Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

11364

Register of Deeds Stamp & File Number

I, Randy Kolehose, in a field survey on January 18 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns: Year, Description, Name, Monument Type. Rows include 1837 G.L.O. Notes Cathcart Set Post, 1902 Survey Williams & Works N/A, 1983 L.C.R.C. #3597 William Byl Set K.C. Monument, 1991 L.C.R.C. #6231 C. Marschall K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 10/24/83 and was recorded per L.C.R.C. #3597.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a Standard Kent County Monument 2.0' North of the C/L of 13 Mile Road (gravel) running East and (bit.) running West per L.C.R.C.'s #3597 and #6231 as set by William Byl midway between the East 1/4 of Section 14 and East 1/4 of Section 23, and 2628' East of the South 1/4 corner of Section 14, which checked the 1902 survey by Williams & Works.

L.C.R.C. #3597

L.C.R.C. #6231

Nail & tag, E sd. 8" Oak N 30 W 39.31'
Nail & tag, W sd. 16" Oak N 65 E 53.74'
Nail & tag, S sd. 30" Oak S 55 E 55.57'
NE cor. shed foundation S 30 W 142.48'

Nail & Tag E. sd. 12" Oak N 36 W 39.19' (39.20')
Nail & Tag N. sd. 24" Hickory N 79 E 143.72' (m. 143.75')
Nail & Tag S. sd. 12" Cherry S 82 E 129.85'
Nail & Tag W. sd. 24" Oak N 59 E 53.61' (m. 53.60')
Nail & Tag SW. sd. 40" Oak S 60 E 55.53'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Kent County Monument

Nail & K.C. remon. tag on E. side 14" Oak N 36° W 39.20'
Nail & K.C. remon. tag on W side 26" Oak N 59° E 53.60'
Nail & K.C. remon. tag on N side 24" Hickory N 80° E 143.75'
Nail & K.C. remon. tag on S side 14" Cherry S 82° E 129.85'
Nail & K.C. remon. tag on SW side 40" Oak S 60° E 55.53'
NE cor. conc. shed fndn. S 30° W 142.45'
Capped iron (G & A #9548) North 33.00'
C/L of bit. and gravel road running E-W, South 2.0'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/29/99
CHAIRMAN [Signature]

Signed by Randy J. Kolehose

Date 5/30/99

Surveyor's Michigan License No. 25854

