

SURVEY & REMONUMENTATION

\$7.00
\$2.00 MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

SECTION

For corners in

Kent (County)	Located in: Courtland Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>10W</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 NOV 14 AM 9:01
REG. OF DEEDS
W. J. ...

10328
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on July 14 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13	1831	G.L.O. Notes	Mullett	Set Post
	1959	Witness Map	K.C. Surveyor	Monument Box
	1972	L.C.R.C. #204	Exxel Engineering	3/4" Iron in Mon. Box
	1981	L.C.R.C. #1721	Williams & Works	Fnd. 3/4" Iron in Mon. Box / Set K.C. Monument
	1991	L.C.R.C. #6227	Chris Marschall	K.C. Monument in Mon. Box

Note: This corner is not common with K-1, T8N, R10W.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/22/97
CHAIRMAN W. J. ...

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 1/13/81 and was recorded per L.C.R.C. #1721.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Found a Standard Kent County Monument on the C/L of 10 Mile Road (bit.) running East and West per L.C.R.C.'s #1721 and #6227 as set by Williams & Works in place of a 3/4" iron they found in a monument box which checked L.C.R.C. #204 and the K.C. Surveyor's records.

L.C.R.C. #1721

L.C.R.C. #6227

K.C. Remon. Tag & Nail in NE Side 18" Walnut N 60°W 71.26'	Nail & Tag N sd. 18" Walnut N 72 W 71.19'
K.C. Remon. Tag & Nail in N Side MBT Service Pole N 75°E 157.43'	Nail & Tag NW sd. U.P. S 65 W 101.61'
K.C. Remon. Tag & Nail in NE Side 28" Oak S 50°E 114.53'	Mon. K-1 T8N 10W N 90 E 92.28'
K.C. Remon. Tag & Nail in N Side P. Pole S 70°W 101.62'	NW cor. Hse. fnd. S 10 W 117.91'
NW Cor. Hse. Fnd. S 20°W 117.99'	SW cor. of 1.5' x 22' stone wall S 35 E top 122.70'
NE Cor. Hse. Fnd. S 10°E 117.16'	Nail & Tag NE sd. 30" Oak S 55 E 116.34'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Standard Kent County Monument

- SW cor. of 1.5' x 22' stone wall S 35° E top 122.70'
- Nail & K.C. remon. tag on N side 18" Walnut N 72° W 71.19'
- NW cor. hse. #8800 fndn. S 10° E 117.91'
- NE cor. hse. #8800 fndn. S 20° W 117.99'
- Nail & K.C. remon. tag on NW side Util. pole S 65° W 101.61'
- K.C. Mon., K-1, T8N, R10W, East 92.28'



Signed by Randy J. Kolehouse Date 9/23/97
EARTH TECH

Surveyor's Michigan License No. 25854