

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kent

(County)

Located In:

Corner Code 11

- | | | |
|------------------------------------|--------------------------|------|
| 1. Public Land Survey | T <u>9N</u> R <u>10W</u> | L-10 |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

93/11/27 01:00

6819
 Register of Deeds Stamp & File Number

I, Wallace E. Glaza, in a field survey on June 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5										
3												
4	7	8										
5												
6	18	17										
7												
8	19	20										
9												
10	30	29										
11												
12	31	32										
13												

A. Description of original monument and accessories and/or subsequent restoration

No previous history on corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-10 (center of Section 25, T9N, R10W, Courtland Township, Kent County, Michigan)
 Set capped rod at intersection of $\frac{1}{4}$ line on previous survey.
 Replaced capped rod with standard 4" x 30" Harrison Monument.

- South $\frac{1}{4}$ corner to center 2648.26'
- West $\frac{1}{4}$ corner to center 2660.97'
- North $\frac{1}{4}$ corner to center 2658.46'
- East $\frac{1}{4}$ corner to center 2659.21'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-10 (4" x 30" Harrison Monument)

- 1) Nail & tag in S. side 16" Oak S80°W 28.12'
- 2) Nail & tag in E. side 16" Hickory S20°W 53.40'
- 3) Nail & tag in S. side fence post N20°E 12.42'
- 4) Nail & tag in W. side 36" Oak N00°E 32.98'
- 5) East-West fence N00°E 7.5'
- 6) Fence to North N90°E 7.0'

Signed by Wallace E. Glaza
 Glaza & Associates, Inc.
 Surveyor's Michigan License No. 31592

Date 7-26-93