

JAN 24 1996 KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County) Located In: Corner Code #

- 1. Public Land Survey T 9N R 10W L-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN COUNTY OF KENT RECEIVED FOR RECORD 95 OCT 24 PM 4:13 Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on June 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-12 1837 GLO Not Set
1972 Consumers Power Co. Int. 1/4 lines - Nothing Set

P.A. 345 1990 KENT COUNTY PEER APPROVED 9/24/95 CHAIRMAN Harry Huber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-12 Found RR Spike. Said RR Spike is on the N-S 1/4 line and is less than 0.1' N. of the E-W 1/4 line of Sec. 36, T9N, R10W. Measurements and angles using the location of the RR Spike agree more or less with surveys by Glaza, All Points, Byl, and D. South.

Note: Consumers Power Co. used a different S 1/4 of Sec. 36 - therefore their measurements differ from others.

The RR Spike is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-12 Set Standard Kent County Monument in place of RR Spike.
Set Nail & KC Remon. tag SE side 12" Walnut S30°W 77.27'
Set Nail & KC Remon. tag S. side 8" Walnut S75°W 35.28'
Rerod & Cap (Glaza) S90°W 33.15'
Set Nail & KC Remon. tag W. side 30" Poplar N30°E 46.65'
C/L N-S Asph. Rd. is West 3'±.
On brush row to East



Signed by Kirk Breitels Date 10/20/95
Surveyor's Michigan License No. 30077