

112

COPY (A)
SECTION

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

SECTION

Kent (County)	Located in: Courtland Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>10W</u>	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS
 1999 OCT 15 AM 8:08
 STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

11382

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randy Kolehouse, in a field survey on February 1 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5	1837	G.L.O. Notes	Cathcart	Set Post
	1963	Notes	MSHD	Monument Box
	1985	L.C.R.C. #4306	R. Kolehouse	Fnd. Iron in Mon. Box / Set K.C. Mon. in Mon. Box
	1991	L.C.R.C. #6218	C. Marschall	K.C. Monument in Mon. Box

Note: This corner is common with A-5, T9N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse on 8/19/85 and was recorded per L.C.R.C. #4306.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found a Standard Kent County Monument in a monument box at the C/L intersection of 14 Mile Road (bit.) running East and West and Ramsdell Drive (bit.) running South and (gravel) running North per L.C.R.C.'s #4306 and #6218 as set by Randy Kolehouse in place of an iron he found in a monument box which checked the 1963 MSHD records.

L.C.R.C. #4306

L.C.R.C. #6218

P.K. Nail in curb joint N 45° W 41.71'
 P.K. Nail in curb joint S 45° W 44.12'
 P.K. Nail in curb joint S 40° E 43.60'

PK Nail in curb joint S 33 W 43.70' (m. 43.64')
 Nail & Tag W sd. 18" Oak S 9 E 255.43'
 NW Corner Bldg. (Proper) Brick 2' above grd. S 59 E 173.20' (m. 173.23')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Standard Kent County Monument in a Monument Box

Nail & K.C. remon. tag on W side P. pole N 14° W 120.89'
 P.K. nail in curb joint N 45° W 41.67'
 P.K. nail in curb joint S 45° E 44.13'
 Nail & K.C. remon. tag on W side 22" Oak S 09° E 255.43'
 NW cor. bldg. (proper) brick 2' abv. Gnd. S 59° E 173.23'
 Fence cor./angle iron N 74° E 218.55'
 Fence cor./angle iron N 10° E 180.21'

On C/L of bit. road running E-W
 On C/L of bit. road running S and gravel road running N

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/25/99

CHAIRMAN *[Signature]*

Signed by *[Signature: Randy J. Kolehouse]*
 EARTH TECH

Date 3/30/99

Surveyor's Michigan License No. 25854

