

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

SECTION

For corners in

Kent (County)	Located in: Courtland Township	Corner Code #
1. Public Land Survey	T 9N R 10W	M-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 OCT 15 AM 8:08

11386

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randy Kolehouse, in a field survey on March 16 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9	1837	G.L.O. Notes	Cathcart	Set Post
	1935	Witness Map	K.C. Surveyor	Boat Spike in 8" Post in Swamp
	1984	L.C.R.C. #3922	William R. Byl	Fnd. "T" Iron in Post / Set K.C. Monument
	1991	L.C.R.C. #6214	Chris Marschall	K.C. Monument

Note: This corner is common with A-9, T9N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 3/19/84 and was recorded per L.C.R.C. #3922.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Found a Standard Kent County Monument in a swamp on the C/L of 12 Mile Road extended West 186' West of the C/L of Ramsdell Drive running North (1.6' under water) per L.C.R.C.'s #3922 and #6214 as set by William Byl which checked the K.C. Surveyor's records.

L.C.R.C. #3922

Nail & tag, N. sd. 24" Oak S 45 E 152.3
Nail & tag, S. sd. 30" Oak N 90 E 159.0'
"T" iron in C/L of Ramsdell Rd. N 90 E 186.4'

L.C.R.C. #6214

Nail & Tag N sd. 26" Oak S 45 E 152.30'
Nail & Tag S sd. 32" Oak N 90 E 159.0'
"T" iron in centerline Ramsdell N 90 E 186.40'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Standard Kent County Monument

- Nail & K.C. remon. tag on N side 26" Oak S 45° E 152.30'
- Nail & K.C. remon. tag on S side 32" Oak N 90° E 159.00'
- "T" iron C/L intersection Ramsdell & 12 Mile N 90° E 186.40'
- SW cor. frame garage at NE cor. Ramsdell & 12 Mile Rd. N 75° E 353.70'

Signed by *Randy J Kolehouse* Date _____

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854

