

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION
KENT COUNTY
(County)

Located In:	Corner Code #
T 9N R 12W	M-2
T R	common with
T 9N R 11W	A-2
T R	
S T R	
S T R	
S T R	
S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:31
REG. OF DEEDS
Lucy Standa

10496

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-2	1837	GLO	Brookfield	Set Post
		Kent Co. Wits		Iron in Mon. Box
	1972	LCRC #357	Spicer	1 1/2" Iron in Mon. Box
	1982	LCRC #3193	Bonnema	Set Kent County Monument in Mon. Box
	1995	LCRC #8329	Breitels	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Harry Tubel*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 12-9-82 and was recorded per LCRC#3193.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Douglas W. Bonnema in place of the 1/2" Iron he found over a large rock inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #357.

LCRC #3193	LCRC #8329		
Nail & Remon. tag P. Pole	S10°W 60.0'	Nail & Remon. tag P. Pole	S10°W 59.99'
Nail & Remon. tag 12" Pine	S60°E 42.20'	Nail & Remon. tag 18" Pine	S60°E 42.24'
Nail & Remon. tag 8" Pine	S65°W 78.85'	Nail & Remon. tag 14" Pine	S65°W 78.44'
Capped Exxel rered at base CP tower N30°E 192.0'		Capped Exxel rered at base CP tower N30°E 192.0'	

C/L E-W blacktop road is North 2.8'
The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag E. side P. Pole	S10°W 59.99'
Nail & KC Remon. tag NE side 20" Pine	S60°E 42.24'
Nail & KC Remon. tag N. side 16" Pine	S65°W 78.39'
Capped Exxel rered in ground at base of S'y leg CP tower	N30°E 192.0'
SE face of gas line marker	N45°W 44.36'
C/L E-W blacktop road is North 2.8'	



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98