

\$7.00  
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:31  
REG. OF DEEDS  
*Lucy Bond*

For corners in

KENT COUNTY  
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 9N R 12W M-6  
T      R      common with  
T 9N R 11W A-6  
T      R
- 2. Property Controlling in Section S      T      R
- 3. Miscellaneous S      T      R
- Property in Sec. S      T      R

10500

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

- M-6 1837 GLO Brookfield Set Post
- 1937 Kent Co. Wits 3/4" Solid Iron
- 1975 LCRC #818 Spicer Mon. Box
- 1977 LCRC #1100 Glaza 3/4" Iron in Mon. Box
- 1982 LCRC #3192 Bonnema Set Kent County Monument in Mon. Box
- 1995 LCRC #8333 Breitels Reset Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98  
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 12-9-82 and was recorded per LCRC#3192.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Kirk Breitels at the same location as set in 1982 by Douglas W. Bonnema in place of the 3/4" Iron and Mon. Box he found. Said Iron in Mon. Box checks with Kent Co. Wits. and LCRC's #818 & #1100.

|  |               |   |
|--|---------------|---|
| LCRC #3192                             |               | LCRC #8333                                      |
| Nail & Remon. tag P. Pole              | West 31.57'   | Nail & Remon. tag P. Pole S90°W 31.70'          |
| Nail & Remon. tag P. Pole              | N10°W 158.82' | Nail & Remon. tag P. Pole N10°W 158.95'         |
| Nail & Remon. tag 8" Poplar            | S16°E 142.15' | Nail & Remon. tag 15" Poplar S16°E 141.73'      |
| Capped Exxel rered @ S. edge rd. S80°E | 83.87'        | Capped Exxel rered @ S. edge rd. S80°E 83.87'   |
| Capped Exxel rered @ E. edge rd. N10°E | 88.47'        | PK Nail & Remon. tag in curb joint N45°E 36.26' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6 Standard Kent County Monument
- Nail & KC Remon. tag N. side P. Pole S90°W 31.70'
- Nail & KC Remon. tag E. side P. Pole N10°W 158.95'
- Nail & KC Remon. tag W. side 18" Poplar S16°E 141.69'
- Capped Exxel rered @ S. edge asph. road S80°E 83.87'
- Nail & KC Remon. tag SE side 4" Pine N50°E 55.35'
- On C/L blacktop roads N-S & E.



Signed by Kirk Breitels

Date 2/19/98

Surveyor's Michigan License No. 30077