

SURVEY & REMONUMENTATION
 \$7.00
 \$2.00
 MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

KENT COUNTY
 (County)

Located in:

Corner Code #

- | | | |
|------------------------------------|----------------------------|------------|
| 1. Public Land Survey | T <u>9</u> N R <u>11</u> W | <u>B-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 98 NOV 16 AM 8:00
 REG. OF DEEDS
W. Glaza

10906

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		●											
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Oct. 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1 1837	GLO	Whitcomb	Not Set
1953	Surveys	Williams & Works	Corner falls in lake - computed location by extending a line from the S 1/4 cor. through the C 1/4 cor. to the Twp. line. Set ref. iron on N-S 1/4 line 363.85' South of computed corner - jog = 257.0'
1994	LCRC #8046	W. Glaza	Corner fall in lake - computed location using prorated GLO distances from the NE cor. of Sec. 6 through the S 1/4 cor. of Sec. 31 T10N R11W to the NW cor. of Sec. 6. Set reference iron on N-S 1/4 line 488.84' S. of computed corner - jog = 381.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 Corner fall in lake. Prorated measurements fit those of W. Glaza. Also found that measurement per Williams & Works method agree ±.

Peer group was in agreement that method used by W. Glaza is a better way of establishing this corner based on other measurements along township line.

The method used by W. Glaza (LCRC #8046) is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 CORNER FALL IN LAKE - NO MONUMENT SET AT THIS CORNER

See LCRC # 10907 for location of witness monument.

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 10/22/98
 CHAIRMAN [Signature]



Signed by [Signature]
 Surveyor's Michigan License No. 30077

Date 11/12/98