

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|--|------------|
| 1. Public Land Survey | T <u>9</u> N R <u>11</u> W | <u>B-2</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

REG. OF DEEDS

Lucy St. Paul

98 NOV 16 AM 8:00

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10908

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- B-2 1837 GLO Not Set
1949 Williams & Works Stone
Steel Post SW 35.75' 18" Sycamore SSW 137.0' P. Pole ESE 128.5' NE cor. school SW 145.2'
Kent Co. Wits Stone
1953-72 Williams & Works Iron
1972 LCRC #357 Spicer 1" Iron
CP Pole S27°W 66.3' 14" Oak S70°E 87.8' 12" Oak N40°E 86.57'
1980 LCRC #1398 Chambers 1 1/2" Iron Pipe
P. Pole S20°W 66.30' 8" Pine S30°E 44.08' 12" Oak S75°E 87.43' 14" Oak N65°E 86.23'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-2 Found 1 1/2" Iron Pipe per the following remaining witnesses:
Nail in P. Pole S20°W 66.30' C/L 14" Pine S30°E 44±
C/L 16" Oak S75°E 87.5± Nail in 20" Oak N65°E 86.10'

Said 1 1/2" Iron Pipe is 16.0' N. and 59.3' E. from Intersection of 1/4 lines and has been used in surveys by Williams & Works, Bueche, Byl, Roosien and Ochs.

The 1 1/2" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-2 Set Standard Kent County Monument in place of the 1 1/2" Iron Pipe.
Nail & KC Remon. tag SW side P. Pole N40°W 29.60'
Nail & KC Remon. tag W. side P. Pole S20°W 66.22'
Nail & KC Remon. tag SW side 14" Pine S30°E 44.02'
Nail & KC Remon. tag S. side 16" Oak S75°E 87.47'
Nail & KC Remon. tag S. side 20" Oak N65°E 86.10'
C/L E-W pavement is South 3' ±

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/22/98
CHAIRMAN Frank Stuber



Signed by *Lucy St. Paul*

Date 11/12/98

Surveyor's Michigan License No. 30077