

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T9N R11W	B-4
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

REG. OF DEEDS

Lucy Bond

98 OCT -7 AM 10:15

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10677

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on June 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

B-4 1837	GLO	Not Set
	Williams & Works	No information
1966	Kent Co. Wits	Iron
	23" Maple ENE 49.35'	Dbl. 10" Oak NE 62.42'
		26" Maple NW 99.93'
1971	Consumers Power	Intersection of 1/4 lines - no corner set

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/23/98

CHAIRMAN *Harry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-4 Found Capped Rerod (Glaza) that is on the N-S 1/4 line and is 0.1' N. of the E-W 1/4 line.

Ed and Wally Glaza have surveyed many parcels in this section using intersection of 1/4 lines (Rerod as found).

Measurements agree with the Glaza surveys and Consumers Power \pm .

Did not find Iron per Kent Co. Wits. nor are there any remaining witnesses.

The Capped Rerod (Glaza) is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-4 Set Standard Kent County Monument in place of the Capped Rerod (Glaza)

- Nail & KC Remon. tag S. side 24" Maple N60°W 43.17'
- Nail & KC Remon. tag SW side 18" Oak N40°W 52.47'
- Nail & KC Remon. tag S. side 30" Maple N55°E 104.88'
- Nail & KC Remon. tag N. side 18" Maple S65°E 79.68'
- Nail & KC Remon. tag E. side 24" Maple S30°W 84.57'
- Rerod - N80°E 5.15'
- N. edge of ditch - South 5'



Signed by *Kirk Breitels*

Date 9/25/98

Surveyor's Michigan License No. 30077