

SURVEY & REMONUMENTATION

MAR 08 1999

\$7.00
\$2.00

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T 9N R 11W	B-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:31
REG. OF DEEDS
Lucy Stord

10509

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7	●												
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

P.A. 345 1930 KENT COUNTY

PEER APPROVED 2/19/98

CHAIRMAN *Harry Puhke*

A. Description of original monument and accessories and/or subsequent restoration:

B-7	1837	GLO	Whitcomb	Set Post
	1950	Kent Co. Wits		Iron in Mon. Box
	1973	LCRC #456	VanKooten	Iron in Mon. Box
	1985	LCRC #4337	Rosema	Set Kent County Monument (removed Mon. Box)
	1990	LCRC #5635	Marschall	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 12-16-85 and was recorded per LCRC #4337.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema in place of the 1/2" Iron inside a Mon. Box he found. Said Iron checks with Kent Co. Wits. and LCRC #456.

LCRC #4337	LCRC #5635
Bottom SE leg CP tower	N43°E 52.65' Nail & Remon. tag 14" Tw. Aspen
Nail & Remon. tag 15" Apple	N04°W 106.84' Bottom SE leg CP metal tower
Nail & Remon. tag 15" Apple	N53°W 136.76' Nail & Remon. tag 18" Apple
Nail & Remon. tag Tw. 18" Aspen	S62°E 140.13' Nail & Remon. tag 18" Apple
NE corner brick garage hse. #3710	S53°W 175.95' NE corner brick garage hse. #3710

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 Standard Kent County Monument			
Nail & KC Remon. tag SW side Tw. 16" Aspen	S66°E	140.18'	
Bottom SE leg CP Co. tower	N38°E	52.66'	
Nail & KC Remon. tag E. side 18" Apple	N09°W	106.85'	
Nail & KC Remon. tag NE side 18" Apple (stump)	N58°W	136.75'	
NE corner brick garage of hse. #3710	S49°W	175.93'	
On centerline E-W asphalt road ±			



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98