

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 9N R 11W B-9
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-9 1837 GLO Whitcomb Set Post
- 1930 Williams & Works Stone
- 1965 Kent Co. Wits Stone
- 1983 LCRC #3400 E. Glaza No desc. of corner
- 1984 LCRC #4022 Rosema Set Kent County Monument
- 1990 LCRC #5636 Marschall Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 11-20-84 and was recorded per LCRC #4022.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9 Found Kent County Monument (Harrison) leaning Westerly, removed and reset per witnesses from above LCRC as set by Maurice J. Rosema in place of the Stone he found. Said Stone checks with Kent Co. Wits., Williams & Works and LCRC #3400.

LCRC #4022

- Nail & Remon. tag 40" Maple N57°E 38.79'
- Nail & Remon. tag 15" Maple S58°E 40.02'
- Nail & Remon. tag dbl. 12" Oak N81°W 30.80'
- Nail & Remon. tag 12" Oak N25°W 38.58'
- Nail & Remon. tag 32" Maple N35°E 60.05'

LCRC #5636

- Nail & Remon. tag 36" Maple N35°E 60.02'
- Nail & Remon. tag 40" Maple N60°E 38.83'
- Nail & Remon. tag 15" Maple S58°E 40.09'
- Nail & Remon. tag 15" Oak N25°W 30.69'
- Nail & Remon. tag 12" Tw. Basswood N80°W 30.69'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9 Standard Kent County Monument

- Nail & KC Remon. tag SE side 36" Maple N35°E 60.02'
- Nail & KC Remon. tag SE side 40" Maple N60°E 38.81'
- Nail & KC Remon. tag SW side 18" Maple S58°E 40.09'
- Nail & KC Remon. tag SW side 18" Oak N25°W 38.53'
- Nail & KC Remon. tag S. side 12" Twin Basswood N80°W 30.79'
- Capped Rerod - Roosien East 33.00'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98

CHAIRMAN [Signature]

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9	●											
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/19/98