

**SURVEY & REMONUMENTATION**

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
38 OCT -7 AM 10:15  
REG. OF DEEDS  
*David Spauld*

For corners in  
KENT COUNTY  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 9N R 11W B-10  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

10680

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on July 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- B-10 1837 GLO Not Set
  - 1902 Williams & Works Set Stone at intersection of 1/4 lines
  - Kent Co. Wits No information
  - 1983 LCRC #3261 Hay "T" Iron at intersection of 1/4 lines
  - NW cor. hse. SE 64.60' CP Pole SW 35.30' NE cor. CP Riser SW 72.90'
  - 1990 LCRC #5627 Meyer "T" Iron found
  - CP Pole S37°W 35.58' Hse. fnd. S35°E 64.60' 40" Oak N54°E 121.25' 35" Maple N60°W 119.88'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 8/20/99  
CHAIRMAN [Signature]

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- B-10 Found "T" Iron over Stone (20" deep) per the following remaining witnesses:
- NW corner house foundation S35°E 64.60'
  - C/L of CP Pole S37°W 35.6'
  - Nail in 40" Maple N60°W 118.90'

Said "T" Iron over Stone is less than 0.1' S. & 0.1' E. of intersection of 1/4 lines and has been used in surveys by Williams & Works, Hay, All Points, and Roosien.

The "T" Iron over Stone is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- B-10 Set Standard Kent County Monument over Stone in place of the "T" Iron
- NW corner house foundation S35°E 64.60'
  - Nail & KC Remon. tag E. side CP Pole S37°W 35.58'
  - Nail & KC Remon. tag S. side 40" Maple N60°W 118.90'
  - Nail & KC Remon. tag N. side stump P. Pole S85°W 132.00'



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 9/25/98