

MAR 08 1999

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE 98 JUL 14 AM 9:54  
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00  
\$2.00

For corners in

KENT COUNTY

Located in:

Corner Code #

*W. J. Bond*  
REG. OF DEEDS

1. Public Land Survey

T 9N R 11W

B-11

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

10643

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on May 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-11 1837	GLO	Whitcomb	Set Post
	Kent Co. Wits		Well Point
1984	LCRC #3722	Wickham	Well Point
1984	LCRC #3789	Byl	Set Kent County Monument
1990	LCRC #5637	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/25/98  
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 3-29-84 and was recorded per LCRC #3789.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the Well Point he found. Said Well Point checks with Kent Co. Wits. and LCRC #3722.  
LCRC #3789  
Nail & Remon. tag 24" Maple clust. N80°E 6.25' Nail & Remon. tag 12" Maple clust. S20°E 33.65'  
Nail & Remon. tag 8" Ash N85°W 7.25' Nail & Remon. tag 24" Maple clust. N80°E 6.46'  
Nail & Remon. tag 8" Maple N00°E 18.55' Nail & Remon. tag 8" Maple N00°W 18.63'  
Nail & Remon. tag 12" Maple clust. S20°E 33.60' Nail & Remon. tag 8" Ash N85°W 7.29'  
Midway between power towers - power lines 100' ± West

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 Standard Kent County Monument  
Nail & KC Remon. tag E. side 12" Maple cluster S20°E 33.65'  
Nail & KC Remon. tag N. side 24" Maple cluster N80°E 6.46'  
Nail & KC Remon. tag W. side 12" Maple N00°E 18.66'  
Nail & KC Remon. tag S. side 10" Ash N85°W 7.29'  
Monument is approx. midway between 2 power towers  
100' ± West of power lines  
Cable foot bridge across river behind house to North of corner.



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 6/25/98