

MAR 08 1998

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T 9N R 11W	C-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

Luci Bond

98 MAR -5 AM 8:32

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10511

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5			4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Jan. 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-2: 1837 GLO Whitcomb Set Post
- 1954 Kent Co. Wits 1" Iron
- 1980 LCRC #1398 Merdzinski "T" Iron
- 1981 LCRC #2452 Jonker Set Kent County Monument
- 1990 LCRC #5640 Marschall Kent Co. Mon.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11-20-81 and was recorded per LCRC #2452.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2 Found Kent County Monument (Harrison) per witnesses from above LCRC as set Robert J. Jonker in place of the "T" Iron over a 1" Iron he found. Both Irons checks with Kent Co. Wits and LCRC #1398.

LCRC #1398	Nail & Remon. tag 12" Oak S30°W 4060'	LCRC #5640	Nail & Remon. tag 14" Oak S26°W 40.53'
	Nail & Remon. tag Guard Post S20°W 17.14		Nail & Remon. tag End Guard Post S14°E 17.64'
	Nail & Remon. tag Guard Post S18°E 17.99'		Nail & Remon. tag End Guard Post S26°E 18.61'
	Nail & Remon. tag 26" Poplar N75°E 86.03'		Nail & Remon. tag 8" Ash N70°E 65.68'
	Nail & Remon. tag 14" Oak N21°W 38.14'		Nail & Remon. tag 16" Oak N23°W 37.81'
	Capped Iron North 33'		Centerline pavement 1' South

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-2 Standard Kent County Monument
- Nail & KC Remon. tag E. side 16" Oak S26°W 40.53'
- Nail & KC Remon. tag E. side End Guard Post S14°W 17.78' (leaning)
- Nail & KC Remon. tag E. side End Guard Post S26°E 18.61'
- Nail & KC Remon. tag S. side 10" Ash N70°E 65.68'
- Nail & KC Remon. tag E. side 16" Oak N23°W 38.05'
- Centerline pavement is 1' South



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/19/98