

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 9N R 11W      C-4  
    T      R  
    T      R  
    T      R
- 2. Property Controlling      S      T      R  
   in Section                    S      T      R
- 3. Miscellaneous            S      T      R  
   Property in Sec.            S      T      R

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-4 1837 GLO Whitcomb Set Post
- 1956 Kent Co. Wits Iron
- 1974 LCRC #728 Nederveld "T" Iron
- 1981 LCRC #2453 Jonker Set Kent County Monument
- 1990 LCRC #5642 Marschall Kent Co. Mon.

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11-20-81 and was recorded per LCRC #2453.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the "T" Iron he found. Said "T" Iron checks with Kent Co. Wits. & LCRC #728.

- |            |   |            |   |
|------------|---|------------|---|
| LCRC #2453 | Nail & Remon. tag 16" Tw. Oak      S27°W 94.40'     | LCRC #5642 | Nail & Remon. tag P.P.      N86°E 25.44'        |
|            | Nail & Remon. tag 8" Ash      N86°W 93.70'          |            | Nail & Remon. tag Tw. 20" Oak      S23°W 94.43' |
|            | Nail & Remon. tag 10" Ash      S58°W 48.06'         |            | Nail & Remon. tag 12" Ash      S55°W 48.01'     |
|            | Chiseled "X" on E. end conc. culv.      S75°E 21.4' |            | Nail & Remon. tag 8" Ash      N70°W 35.86'      |
|            | C/L N-S B.T. West 6 1/2' ±                          |            |   |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-4 Standard Kent County Monument
- Nail & KC Remon. tag N. side P. Pole      N86°W 25.44'
- Nail & KC Remon. tag E. side Twin 24" Oak      S23°W 94.43'
- Nail & KC Remon. tag NW side 16" Ash      S55°W 47.98'
- Nail & KC Remon. tag NE side 12" Ash      N70°W 35.90'



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 2/19/98

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 98 MAR -5 AM 8:32  
 REG. OF DEEDS  
 [Signature]  
 10512  
 Register of Deeds Stamp & File Number

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |