

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T9N R11W      C-10  
                                   T      R  
                                   T      R  
                                   T      R
- 2. Property Controlling    S      T      R  
    in Section               S      T      R
- 3. Miscellaneous           S      T      R  
    Property in Sec.         S      T      R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 93 MAY 21 AM 8:31  
 REG. OF DEEDS  
*Lucy Bond*

10601

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Kirk Breitels, in a field survey on April 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-10 1837 GLO	Whitcomb	Set Post
Kent Co. Wits		Iron
1972 LCRC #219	Spicer	1" Iron
1981 LCRC #2457	Jonker	Set Kent County Monument
1990 LCRC #5648	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 4/30/98  
 CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11-20-81 and was recorded per LCRC #2457.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Iron over a 1" Iron inside a 1 1/2" Iron he found. All Irons check with Kent Co. Wit. and LCRC #219.	
LCRC #2457	LCRC #5648
Nail & Remon. tag P. Pole S40°E 41.10'	Nail & Remon. tag Util. Pole S40°E 41.11'
Nail & Remon. tag 36" Oak N70°E 73.12'	Nail & Remon. tag 38" Oak N67°E 73.13'
Nail & Remon. tag P. Pole N00°W 98.53'	Nail & Remon. tag P. Pole N05°W 98.48'
Nail & Remon. tag P. Pole S75°W 101.19'	Nail & Remon. tag Tel. Pole S75°W 101.14'
C/L "X" Pavement is 2' South	C/L "X" is 2' South

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10 Standard Kent County Monument	
Nail & KC Remon. tag SW side Util. Pole S40°E 41.23'	
Nail & KC Remon. tag S. side 42" Oak N67°E 73.16'	
Nail & KC Remon. tag W. side P. Pole N05°W 98.73'	
Nail & KC Remon. tag NW side Tel. Pole S75°W 101.14'	
C/L "X" pavement is 2' South	



Signed by *Kirk Breitels*  
 Surveyor's Michigan License No. 30077

Date 4/30/98