

\$7.00 MAR 08 1999
\$2.00

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:32
REG. OF DEEDS
Lucy Board

For corners in

KENT COUNTY (County)	Located in:	Corner Code #
1. Public Land Survey	T9N R11W	C-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

10515

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-11 1837 GLO	Whitcomb	Set Post
1942 Kent Co. Wits		Iron
1973 LCRC #475	Spicer	"T" Iron
1981 LCRC #2458	Jonker	Set Kent County Monument
1990 LCRC #5649	Marschall	Kent Co. Mon.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Harry Hubert*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11-25-81 and was recorded per LCRC #2458.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Iron over a Stone he found. Said Iron and Stone checks with LCRC #475.

LCRC #2458	LCRC #5649
Nail & Remon. tag 12" Elm West 19.00'	Nail & Remon. tag top Guard Rail Post N33°W 30.54'
Nail & Remon. tag 14" Oak S15°W 91.28'	Nail & Remon. tag top Guard Rail Post N87°W 15.96'
Nail & Remon. tag 9" Elm N59°E 86.65'	Nail & Remon. tag top Guard Rail Post S35°W 29.33'
Nail & Remon. tag 7" Elm S20°E 87.38'	Nail & Remon. tag 14" Elm N55°E 86.63'
Nail & Remon. tag 8" Elm N31°E 82.39'	Nail & Remon. tag 12" Ash N24°E 111.87'
C/L N-S grav. is E 5'±, On C/L BT to E.	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 Standard Kent County Monument	
Nail & KC Remon. tag Top of N. Guard Rail Post	N33°W 30.54'
Nail & KC Remon. tag Top of Guard Rail Post	N87°W 16.25'
Nail & KC Remon. tag Top of S. Guard Rail Post	S35°W 29.76'
Nail & KC Remon. tag NW side 18" Elm	N55°E 86.60'
Nail & KC Remon. tag W. side 14" Ash	N24°E 111.92'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98