

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

Located In:	Corner Code #
T9N R 11W	C-13
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 9:00

REG. OF DEEDS

Lucy Bond

9131
Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Jan. 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/17/96
CHAIRMAN Harry Hubers

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-13	1837	GLO	Brookfield	Set Post
	1944	Kent Co. Wit.		Iron-Mon. Box
	1973	LCRC #462	Spicer	Mon. Box
	1981	LCRC #1718	Merdzinski	Set Kent County Monument
	1984	LCRC #2809	Jonker	Set Kent Co. Mon. after const.
	1990	LCRC #5651	Marschall	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/7/81 and was recorded per LCRC #1718

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski (Reset 1984 by Jonker) in place of the 1 1/2" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC #462.

LCRC #1718	LCRC #5651
Nail/tag signal pole S40°E 54.24'	C/L USGS Mon. S49°W 76.46'
SW cor. frame hse. N40°E 165.6'	SW cor. hse. fnd. N50°E 186.38'
LCRC #2809	"X" on culv. N72°E 112.30'
Nail/tag signal pole N40°W 74.78'	"X" on culv. S70°E 105.74'
C/L USGS Mon. S50°W 76.5'	"X" top stone fence N30°W 97.13'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 Standard Kent County Monument	
C/L USGS Monument	S49°W 76.46'
SW cor. house foundation	N50°E 186.38'
"X" chiseled W. end conc. culv.	N72°E 112.30'
"X" chiseled W. end conc. culv.	S70°E 105.74'
"X" chiseled top NE cor. stone fence cor.	N30°W 97.13'
Set Nail & KC Remon. tag SW side Guy Pole	S40°E 54.68'
Set Nail & KC Remon. tag SW side Guy Pole	N40°W 74.93'
Kent Co. Mon. (C-1, T8N, R11W)	East 440.93'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/1/96