

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

KENT COUNTY

(County)

Located in:

Corner Code #

- |                                    |              |               |     |
|------------------------------------|--------------|---------------|-----|
| 1. Public Land Survey              | T <u>9</u> N | R <u>11</u> W | D-6 |
|                                    | T            | R             |     |
|                                    | T            | R             |     |
|                                    | T            | R             |     |
| 2. Property Controlling in Section | S            | T             | R   |
|                                    | S            | T             | R   |
| 3. Miscellaneous Property in Sec.  | S            | T             | R   |
|                                    | S            | T             | R   |

REG. OF DEEDS

*Luci Stand*

38 NOV 16 AM 8:00

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

10913

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Oct. 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-6 1837 GLO	Not Set
Williams & Works	No information
1944-56 Kent Co. Wits	1 1/2" Pipe in Mon. Box
18" Maple NW 31.84'	28" Elm W 96.8'
19" Hickory SE 61.19'	26" Elm E 38.00'
14" Maple E 27.35'	F.P. W 31.23'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 10/22/98  
CHAIRMAN *Harry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-6 Found 3/4" Iron Pipe in Mon. Box - one remaining witness: F.P. W 31.7' (also found new wit. nails in trees, etc.)

Said Iron Pipe in Mon. Box is 3.1' W. and 3.2' N. of Intersection of 1/4 lines and agrees with measurements of others.

The 3/4" Iron Pipe in Mon. Box is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-6 Set Standard Kent County Monument in Mon. Box in place of the 3/4" Iron Pipe.

Nail & KC Remon. tag NE side cluster 6" Elms	N15°W	82.79'
Nail & KC Remon. tag W. side P. Pole	N10°E	248.36'
Nail & KC Remon. tag SW side P. Pole	S30°E	54.78'
Nail & KC Remon. tag S. side new fence post	S90°W	36.37'
Nail & KC Remon. tag SE side Tri. 8" Elm	S55°W	41.25'
On C/L N-S asphalt road		



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 11/12/98