

MAR 08 1999

\$7.00
\$2.00

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 9N R 11W D-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breiteis, in a field survey on Feb. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-7	1837	GLO	Whitcomb	Set Post
	1968	Kent Co. Wits		Iron in Mon. Box
	1980	LCRC #1359	Merdzinski	5/8" Iron in Mon. Box
	1981	LCRC #2460	Jonker	Set Kent County Monument in Mon. Box
	1990	LCRC #5655	Marschall	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11-20-81 and was recorded per LCRC #2460.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 5/8" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #1359.

LCRC #2460	Nail & Remon. tag P. Pole	S48°W	61.80'	Cut "X" on S. end conc. end section	S61°E	73.49'
	Nail & Remon. tag G. Pole	N48°E	71.30'	Nail & Remon. tag P. Pole	S39°E	56.62'
	Nail & Remon. tag curb joint	S42°E	45.39'	Nail & Remon. tag P. Pole	S45°W	65.73'
	Nail & Remon. tag curb joint	N45°W	45.59'	Cut "X" on N. end conc. end section	N61°E	68.34'
	On C/L "X" pavement			Nail & Remon. tag in curb joint	S45°E	45.40'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7 Standard Kent County Monument in Mon. Box

"X" cut on top of S. end conc. culvert	S61°E	73.49'
Nail & KC Remon. tag NE side P. Pole	S39°E	56.62'
Nail & KC Remon. tag NW side P. Pole	S45°W	65.73'
Nail & KC Remon. tag NE side 18" Elm	N40°W	100.05'
Nail & KC Remon. tag NW side Guy Pole	N48°E	71.24'

On C/L E-W & N-S asphalt roads ±

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:32
REG. OF DEEDS
W. J. ...

10518

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7			●									
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

P.A. 345 1930 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Harry Stuber*

Signed by *Kirk Breiteis*
Surveyor's Michigan License No. 30077

Date 2/19/98

