

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>9</u> N	R <u>11</u> W	D- <u>9</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-9 1837 GLO Whitcomb Set Post
- 1879-1963 Williams & Works Post-Iron-Mon. Box
- 1946 Kent Co. Wits Iron in Mon. Box
- 1983 LCRC #3671 Bueche Set Kent County Monument
- 1990 LCRC #5657 Marschall Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12-12-83 and was recorded per LCRC #3671.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-9 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Iron inside a Mon. Box he found. Said Iron in Mon. Box checks with Williams & Works and Kent Co. Wits.
- LCRC #3671 LCRC #5657
- "X" in conc. culv. S70°E 34.60' "X" in conc. culv. S70°E 34.55'
- Conc. Plat Mon. N90°W 50.0' Conc. mon. plat cor. N90°W 49.93'
- Nail & Remon. tag 10" Cherry S20°W 97.84' Nail & Remon. tag 6" Maple N60°W 51.97'
- Nail & Remon. tag 8" Oak N60°W 52.00' Nail & Remon. tag 8" Ash N30°W 68.73'
- Nail & Remon. tag 8" Oak N30°W 68.79' Nail & Remon. tag 10-8-8 Tri. Elm S20°W 97.82'
- On C/L blacktop road N-S On centerline blacktop N-S

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-9 Standard Kent County Monument
- "X" in concrete culvert S70°E 34.63'
- Concrete Mon. Plat Corner N90°W 49.93'
- Nail & KC Remon. tag S. side 10" Maple N60°W 51.94'
- Nail & KC Remon. tag NE side 12" Ash N30°W 68.77'
- Nail & KC Remon. tag W. side 10" Ash S20°E 72.17'

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:32  
REG. OF DEEDS  
*Luigi Bond*

10519

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98

CHAIRMAN *[Signature]*



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/19/98