

SURVEY & REMONUMENTATION
 \$7.00
 \$2.00
 MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**
KENT COUNTY

Located In:	Corner Code #
1. Public Land Survey	T 9N R 11W D-12
	T R
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 98 NOV 16 AM 8:00
 REG. OF DEEDS
Lucy Bond

10914
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-12 1837 GLO	Not Set
Williams & Works	No information
Kent Co. Wits	No information
1984 Survey Glaza	Set Iron at Intersection of 1/4 lines

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 9/24/98
 CHAIRMAN *Harry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-12 Found Capped Rerod (Glaza) - 0.7' W. and 0.7' S. of Intersection of 1/4 lines. Measurements in the Section by Glaza and other surveyors fit better with the computed Intersection of 1/4 lines rather than the Capped Rerod as found. Since this Capped Rerod has not been recorded as the corner, I recommend using the Intersection of 1/4 lines as the location of the corner as originally intended by Glaza.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-12 Set Standard Kent County Monument at Intersection of 1/4 lines.

Nail & KC Remon. tag SW side 12" Ash	S55°E 15.00
Nail & KC Remon. tag N. side 22" Maple	N65°E 16.60'
Nail & KC Remon. tag W. side 22" Ash	N30°W 17.42'
Nail & KC Remon. tag NE side 14" Maple	N75°W 37.69'
Nail & KC Remon. tag S. side 18" Maple	S65°W 43.41'
N. edge of Roguc River (now located) is South 20' ±	



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 11/12/98