

\$7.00
\$2.00

SURVEY &
REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

KENT COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 9N R 11W E-4
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on April 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-4	1837	GLO	Whitcomb	Set Post
	1976	LCRC #3403	Glaza	No desc. of corner - witnesses given.
	1983	LCRC #3550	Glaza	1" Iron
	1985	LCRC #4316	Rosema	Set Kent County Monument
	1990	LCRC #5662	Marshall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 4/30/98
CHAIRMAN Harry Hubert

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 11-15-85 and was recorded per LCRC #4316.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 Found BROKEN Kent County Monument (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema in place of the 3/4" Iron over a 1/2" Iron he found. Both Irons check with LCRC's #3403 & #3550. Removed & Replace Kent Co. Monument.

LCRC #4316	Nail & Remon. tag 12" Oak N43°E 31.50'	LCRC #5662	Nail & Remon. tag 16" Oak S82°W 18.74'
	Nail & Remon. tag 10" Oak S36°E 35.48'		Nail & Remon. tag 16" Oak N40°E 31.50'
	Nail & Remon. tag 15" Oak S22°E 60.96'		Nail & Remon. tag 12" Ash S39°E 35.46'
	Nail & Remon. tag 15" Oak S17°E 78.04'		Nail & Remon. tag 14" Ash S25°E 60.93'
	Nail & Remon. tag 18" Oak S86°W 18.77'		Nail & Remon. tag 18" Ash S20°E 78.02'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-4 Standard Kent County Monument
- Nail & KC Remon. tag S. side 18" Oak S82°W 18.74'
- Nail & KC Remon. tag N. side 18" Oak N40°E 31.57'
- Nail & KC Remon. tag SW side 14" Ash S39°E 35.46'
- Nail & KC Remon. tag W, side 16" Ash S25°E 60.93'
- Nail & KC Remon. tag W. side 20" Ash S20°E 78.04'
- Capped Rod - East 33.03'
- On C/L N-S gravel road ±
- On tree row to E & W



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 4/30/98

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAY 21 AM 8:31
REG. OF DEEDS

10605

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													