

STONEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAY 21 AM 8:31
REG. OF DEEDS
Lucy Standa

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 9N R 11W E-6
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

10606

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17	●	16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Kirk Breitels, in a field survey on Feb. 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6	1837	GLO	Whitcomb	Set Post
	1984	LCRC #3802	Bueche	Set Kent County Monument
	1990	LCRC #5646	Marschall	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 4-21-84 and was recorded per LCRC #3802.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 4/30/98
CHAIRMAN *Henry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche.

LCRC #3802		LCRC #5646
Face of 12" dia. fence post	South 0.40'	Nail & Remon. tag 24" Oak N90°E 11.13'
Nail & Remon. tag 24" Oak	N90°E 11.15'	Nail & Remon. tag 14" Beech N50°E 32.11'
Nail & Remon. tag 14" Beech	N50°E 32.12'	Nail & Remon. tag 10" Maple N30°W 25.74'
Nail & Remon. tag 10" Maple	N30°W 25.71'	Nail & Remon. tag 24" Oak N70°W 32.14'
Nail & Remon. tag 24" Oak	N70°W 32.10'	Nail & Remon. tag 28" Oak S15°E 28.61'
Nail & Remon. tag 28" Oak	S15°E 28.68'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 Standard Kent County Monument

Nail & KC Remon. tag N. side 24" Oak stump	N90°E 11.16'
Nail & KC Remon. tag SE side 18" Beech	N50°E 32.11'
Nail & KC Remon. tag SW side 14" Maple	N30°W 25.74'
Nail & KC Remon. tag S. side 26" Oak	N70°W 32.10'
Nail & KC Remon. tag E. side 30" Oak	S15°E 28.61'

Face of 12" dia. fence post is South 0.4'
Near A-frame "cottage"



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 4/30/98