

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>9</u> N R <u>11</u> W	E-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECORDED FOR RECORD

93 MAR -5 AM 8:32

REG. OF DEEDS

Lucy Stand

10523

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-7	1837	GLO	Whitcomb	Set Post
	1970	Kent Co. Wits		Mon. Box
	1983	LCRC #3673	Bueche	Set Kent County Monument in Mon. Box
	1990	LCRC #5665	Marschall	Kent County Monument

P.A. 345 1998 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Harry Duke

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12-12-83 and was recorded per LCRC #3673.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits.
LCRC #3673 LCRC #5665

Nail & Remon. tag top g. rail post N65°W 64.44'	Nail & Remon. tag P. Pole S02°W 42.10'
Nail & Remon. tag top g. rail post N45°W 32.40'	Nail & Remon. tag top 6"x8" guard post N45°W 32.38'
Nail & Remon. tag top g. rail post N10°E 23.36'	Nail & Remon. tag top 6"x8" guard post N70°W 64.46'
Nail & Remon. tag top g. rail post N55°E 35.90'	Nail & Remon. tag top 6"x8" guard post N05°E 23.37'
Nail & Remon. tag top g. rail post N70°E 57.27'	Nail & Remon. tag top 6"x8" guard post N49°E 35.90'
On C/L blacktop road E-W	Nail & Remon. tag top 6"x8" guard post N66°E 57.22'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag W. side P. Pole	S02°W 42.13'
Nail & KC Remon. tag in top of guard rail post	N45°W 32.38'
Nail & KC Remon. tag in top of guard rail post	N70°W 64.46'
Nail & KC Remon. tag in top of guard rail post	N05°E 23.37'
Nail & KC Remon. tag in top of guard rail post	N49°E 35.90'
Nail & KC Remon. tag in top of guard rail post	N66°E 57.29'
On C/L E-W asphalt road	



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98