

SURVEY &
REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|--------------|---------------|------|
| 1. Public Land Survey | T <u>9</u> N | R <u>11</u> W | E-10 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

98 MAR -5 AM 8:33

REG. OF DEEDS

Lucy Bond

10525

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|------|------|---------------|-----------|--------------------------|
| E-10 | 1837 | GLO | Whitcomb | Set Post |
| | | Kent Co. Wits | | 3" Iron |
| | 1972 | LCRC #220 | Spicer | 1 1/2" Iron |
| | 1981 | LCRC #2463 | Jonker | Set Kent County Monument |
| | 1990 | LCRC #5668 | Marschall | Kent Co. Mon. |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Harry Hubert*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11-20-81 and was recorded per LCRC #2463.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1 1/2" over a 3" Iron he found. Both Irons check with Kent Co. Wits. and LCRC #220.

- | | | | |
|------------|--|------------|---|
| LCRC #2463 | Nail & Remon. tag 20" Maple N02°W 29.02' | LCRC #5668 | Nail & Remon. tag 24" Oak S07°E 31.13' |
| | Nail & Remon. tag 6" Hickory N31°E 30.50' | | Nail & Remon. tag 22" Maple N02°W 28.70' |
| | Nail & Remon. tag 20" Oak S06°E 31.12' | | Nail & Remon. tag 8" Hickory N32°E 30.49' |
| | Nail & Remon. tag 20" Oak S72°E 124.65' | | Nail & Remon. tag 22" Oak S70°E 124.55' |
| | On C/L E-W B.T. and in line tree row North | | NW corner brick garage S30°W 145.24' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|-------|---------|
| E-10 Standard Kent County Monument | | |
| Nail & KC Remon. tag W. side 26" Oak | S07°E | 31.13' |
| Nail & KC Remon. tag E. side 24" Maple | N02°W | 28.70' |
| Nail & KC Remon. tag SE side 10" Hickory | N32°E | 30.52' |
| Nail & KC Remon. tag N. side 24" Oak | S70°E | 124.83' |
| NW corner brick garage (#1580) | S30°W | 145.29' |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98