

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY
(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>9</u> N	R <u>11</u> W	<u>F-2</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	_____
	S _____	T _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____	_____
	S _____	T _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 NOV 16 AM 8:00
REG. OF DEEDS
David Spauld

10915

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on July 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-2	1837	GLO	Not Set
		Williams & Works	No information
		Kent Co. Wits	No information
1977	LCRC #1094	VanKooten	Found 3/4" Iron Pipe 6' North of centerline of road
		12" Maple SW 59.19'	18" Oak SE 70.91'
			P. Pole NNE 46.80'
			Iron South 32.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-2 Found 3/4" Iron Pipe per the following remaining witnesses:
Nail in 16" Maple SW 59.19'
Nail in 27" Oak SE 70.70'
Iron Pipe S 32.76'

Said 3/4" Iron Pipe is 0.4' E. & 0.1' N. of intersection of 1/4 lines and has been used in surveys by Medema & VanKooten, All Points and Hackbardt.

The 3/4" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-2	Set Standard Kent County Monument in place of the 3/4" Iron Pipe
	Nail & KC Remon. tag E. side P. Pole N25°E 45.55'
	Nail & KC Remon. tag SE side 16" Maple S45°W 59.19'
	Nail & KC Remon. tag W. side 22" Oak S20°W 55.61'
	Nail & KC Remon. tag NE side 27" Oak S40°E 70.70'
	1/2" Iron Pipe South 32.76'
	C/L E-W blacktop road is South 6' ±

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/20/98
CHAIRMAN [Signature]



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 11/12/98