

**SURVEY & REMONUMENTATION**

**KENT COUNTY REMONUMENTATION**

\$7.00  
\$2.00

MAR 08 1999

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>9</u> N R <u>11</u> W	F-4
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

38 NOV 16 AM 8:00

REG. OF DEEDS

*Lucy Standa*

**10916**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Sept. 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

F-4 1837 GLO Not Set  
1895 Williams & Works Old stake in center of fences - 2654' W. of E 1/4 cor.  
Kent Co. Wits No Information

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

F-4 Established Intersection of 1/4 lines and found nothing at corner. Location is on fence line to North  $\pm$  and fence to West is 8' North  $\pm$ .

Measured 2653.13' W. of E 1/4 corner (2653' Williams & Works 1895).

Location agrees with measurements of Hackbardt, Glaza, Roosien and Fricke.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

F-4 Set Standard Kent County Monument at the Intersection of 1/4 lines.

Nail & KC Remon. tag SE side 20" Oak S55°W 7.59'  
Nail & KC Remon. tag W. side 30" Basswood N00°E 8.82'  
Nail & KC Remon. tag NW side 10" Cherry N60°E 41.33'  
Nail & KC Remon. tag S. side 8" Basswood S80°E 50.51'  
Nail & KC Remon. tag S. side Tri. 3" Oak N45°W 29.27'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 9/24/98

CHAIRMAN Harry Huber



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 11/12/98