

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T9N R11W F-9
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

99 MAY 21 AM 8:31

REG. OF DEEDS

Lucy St. Paul

10609

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on March 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- F-9 1837 GLO Whitcomb Set Post
- Kent Co. Wits Leaded Stone
- 1979 LCRC #1250 Merdzinski Iron
- 1981 LCRC #2465 Jonker Set Kent County Monument
- 1990 LCRC #5676 Marschall Reset Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 4/30/98
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11-25-81 and was recorded per LCRC #2465.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 Found BROKEN Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Concrete Spike in side a 3/4" Iron he found. Said Spike & Iron checks with Kent Co. Wits. and LCRC #1250. Removed and replaced broken portion of Kent Co. Mon.

LCRC #2465		LCRC #5676
Nail & Remon. tag 8" Oak	S08°E 40.50'	Nail & Remon. tag 10" Oak S12°E 40.55'
Nail & Remon. tag 14" Maple	N33°E 34.43'	Nail & Remon. tag 12"-10" Tw. Maple S64°W 47.99'
Nail & Remon. tag 15" Beech	N22°W 65.51'	Nail & Remon. tag 20" Maple N31°E 34.26'
Nail & Remon. tag 15" Ash	N42°W 52.19'	Nail & Remon. tag 18" Beech N22°W 65.39'
Nail & Remon. tag 6" Tw. Maple	S66°W 48.36'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-9 Standard Kent County Monument
- Nail & KC Remon. tag E. side 14" Oak S12°E 40.57'
- Nail & KC Remon. tag N. side Tw. 14" Maple S64°W 47.96'
- Nail & KC Remon. tag SE side 24" Maple N31°E 34.30'
- Nail & KC Remon. tag S. side 15" Birch N60°W 68.10'
- Nail & KC Remon. tag NE side Clump 8"-15" Oaks S40°E 53.05'
- On C/L E-W gravel road ±



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 4/30/98