

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 9N R 11W G-3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:33
REG. OF DEEDS
David J. ...

10533

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Jan. 2, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4			3		2		1		
3												
4	7	8	9			10		11		12		
5												
6	18	17	16			15		14		13		
7												
8	19	20	21			22		23		24		
9												
10	30	29	28			27		26		25		
11												
12	31	32	33			34		35		36		
13												

A. Description of original monument and accessories and/or subsequent restoration:

- G-3 1837 GLO Whitcomb Set Post
- 1961 Kent Co. Wits 1" Iron in Mon. Box
- 1976 LCRC #1010 Nederveld Mon. Box
- 1981 LCRC #2467 Jonker Set Kent County Monument
- 1990 LCRC #5681 Marschall Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98

CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11-20-81 and was recorded per LCRC #2467.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #1010.

- | | |
|--|---|
| LCRC #2467 | LCRC #5681 |
| C/L top conc. R.O.W. marker S72°E 121.19' | C/L top conc R.O.W. marker S73°W 121.21' |
| C/L top conc. R.O.W. marker S20°W 121.62" | Vertical cut top conc. culv. N68°W 73.49' |
| C/L top conc. R.O.W. marker S20°E 57.5' | Vertical cut top conc. culv. N68°E 71.76' |
| Nail & Remon. tag P. Pole S75°E 121.86' | Nail & Remon. tag P.P. S78°W 121.74' |
| Vertical chisel cut conc. culv. N72°E 71.77' | C/L of N-S road is East 1' ± |
| Vertical chisel cut conc. culv. N74°W 73.5' | |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-3 Standard Kent County Monument
- C/L top conc. R.O.W. marker S73°W 121.21'
- Chiseled "X" top conc. culv. N68°W 73.41'
- Chiseled "X" top conc. culv. N68°E 71.77'
- Chiseled "X" top conc. culv. S65°E 70.42'
- C/L N-S road is East 1' ±



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98